



Alaska Railroad Corporation
327 W. Ship Creek Ave.
Anchorage, AK 99501

April 3, 2025

Addendum 4
ITB #25-18-213091
Ship Creek Bridge 114.3 Replacement

**Addendum number 4 has been issued for correction on base bid item 505.0006.1.
New base bid items list provided.**

The Closing Date for this ITB was changed in Addendum 2.
Bids will be received until April 8, 2025 @ 3:00 PM Alaska time.

1. NEW BASE BID ITEMS LIST – Line 505.0006.1 was changed from a quantity of 10 to 4.

All other terms and conditions remain unchanged.
If there are any questions regarding this addendum, please let me know.

Thank you,

Rob Walker

Logistics Manager
Alaska Railroad Corporation

BASE BID ITEMS

| Item No. | Item Description | Unit | Quantity ¹ | Unit Bid Price | Amount Bid |
|-----------------|--|-------------|------------------------------|-----------------------|-------------------|
| 640.0001.1 | Mobilization and Demobilization | LS | 1 | | |
| 201.0003.1 | Clearing | ACRE | 0.5 | | |
| 202.001.1 | Removal of Structures and Obstructions | LS | 1 | | |
| 205.0001.1 | Excavation for Structures | CY | 660 | | |
| 301.0005.1 | Railroad Sub-Ballast, Grading C-1 | TON | 25 | | |
| 304.0005.1 | Subbase, Grading A | TON | 118 | | |
| 309.0001.1 | Railroad ballast, Type 3 | TON | 815 | | |
| 309.0001.2 | Railroad ballast, Type 5 | TON | 157 | | |
| 501.0001.1 | Class A Concrete | LS | 1 | | |
| 501.0008.1 | Precast Concrete, Member (ALL) | LS | 1 | | |
| 501.0004.1 | Class DS Concrete, 42" Dia. Pipe Fill | LF | 400 | | |
| 501.0004.2 | Class DS Concrete, 48" Dia. Pipe Fill | LF | 440 | | |
| 503.0001.1 | Reinforcing Steel | LS | 1 | | |
| 504.0002.1 | Structural Steel | LS | 1 | | |
| 505.0005.1 | Furnish Structural Steel Piles, 42" Pipe | LF | 636 | | |
| 505.0005.2 | Furnish Structural Steel Piles, HP14X89 | LF | 120 | | |
| 505.0005.3 | Furnish Structural Steel Piles, 48" Pipe | LF | 914 | | |
| 505.0006.1 | Drive Structural Steel Piles, 42"Pipe | EA | 4 | | |
| 505.0006.2 | Drive Structural Steel Piles, HP14X89 | EA | 4 | | |
| 505.0006.3 | Drive Structural Steel Piles, 48"Pipe | EA | 6 | | |
| 508.0001.1 | Waterproofing Membrane | LS | 1 | | |
| 611.0001.1 | Riprap, Class II | CY | 200 | | |
| 618.0004.1 | Seeding | SY | 2250 | | |
| 631.0002.1 | Geotextile Stabilization, Class 1 | SY | 130 | | |

| | | | | | |
|-------------------------|--|----|------|-----------|-----------|
| 641.001.1 | Erosion, Sediment, and Pollution Control | LS | 1 | | |
| 641.0002.1 | Temporary Erosion, Sediment, and Pollution Control | CS | 1 | \$120,000 | \$120,000 |
| 642.0001.1 | Construction Surveying | LS | 1 | | |
| 643.0002.1 | Traffic Maintenance | LS | 1 | | |
| 646.0001.1 | CPM Scheduling | LS | 1 | | |
| 647.0001.1 | As-Built Drawings and Specifications | LS | 1 | | |
| 691.0001.1 | Temporary Site Access and Structures | LS | 1 | | |
| 802.0001.1 | Track Work, 115# RE Rail | TF | 240 | | |
| 802.0005.1 | Track Tamping, Surfacing, and Final Dressing | TF | 2300 | | |
| Total Base Bid : | | | | | |